

Veterans Plaza Reroof



Project Description:

The project was a restoration of the existing roof membrane that addressed long term maintenance issues and leaks in the plaza roof. The existing membrane & insulation were covered using a fluid applied, low VOC, polyurethane membrane with a 20 year warranty. A base coat, reinforcement fabric & top coat were applied over the existing rubber roof to make a combined 140mil thick membrane. Allowing the existing roof membrane & remediated insulation to remain in place diverted over 200 tons of construction waste from the landfill. The light color roofing lowers summertime heat absorption reducing air conditioning loads.



Design Team:

Weatherproofing
Technologies/Tremco

Total Project Cost:

\$2,114,893.57

Contractor Team:

Weatherproofing
Technologies/Tremco

Completion Date:

November 2020



Jim Durrett
County Mayor

Nick Powell, P.E.
County Engineer