

ADDENDUM NO. 1
SALEM ROAD OVER A LOCAL BRANCH: MONTGOMERY COUNTY, TN

Addendum Date and Time: July 9, 2024, 10:30 AM CST

By: Winford A. Petrone

THE FOLLOWING ITEMS AND CLARIFICATIONS ARE HEREBY TO BE INCORPORATED AS PART OF THE CONTRACT DOCUMENTS FOR THE ABOVE REFERENCED PROJECT:

PLANS SHEET S2, Footnotes under Estimated Quantities:

NOTE 1- Replace Note 1 as follows: "The removal of existing structures includes removal of 2 runs of 42" reinforced concrete pipe, and 1 run of 40" corrugated metal pipe. Each existing pipe is approximately 40 feet in length."

NOTE 5-Replace Note 5 as follows: "Includes forming and placement of all box culvert concrete in accordance with the project specifications." (i.e., there is no special excavation to preserve a nearby tree.)